


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Decatur County. Sec. 25 Twp. 1 Rge. 26 (E) (W)
Location as "NE/CNW/SW" or footage from lines C SW SW NW
Lease Owner Sauvage Drilling Co. Inc.
Lease Name Mizell Well No. 1
Office Address Oberlin, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 6 19 62
Application for plugging filed " " 19 62
Application for plugging approved " " 19 62
Plugging commenced " " 19 62
Plugging completed " " 19 62
Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	206	8 5/8	206	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug at 500 ft. with one sack hulls and 20 sacks cement. Filled the hole with heavy mud to 206 ft. and set plug with one sack hulls and 20 sacks cement. Filled hole to 20 ft. with heavy mud and set plug with 1 sack hulls and 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 3 1963

1-3-63
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sauvage Drilling Company, Inc.
Address Oberlin, Kansas

STATE OF Kansas, COUNTY OF Decatur, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
(Address) _____

SUBSCRIBED AND SWORN TO before me this 2 day of January, 1963

My commission expires October, 1966
Elsie Smith
Notary Public.



Operator _____ Sausage Drilling Co., Inc.
Farm Name — Mizell Rotary Drilling Equipment
Well No. — 1 Oberlin, Kansas
Contractor — Company Tools
Rotary Commenced — 11-30-62
Rotary Completed — 12-6-62

Location C SW SW NW 25-1-26W
Decatur County, Kansas
Casing Record
206 Feet of 8 5/8"
Surface Casing

15-039-00183-00-00

Figures denote bottom of formation

Shale & Sand1027 Ft.
Shale, Sand & Pyrite,.....1824 Ft.
Anhydrite.....2055 Ft.
Shale & Sand.....2485 Ft.
Shale & Lime.....2809 Ft.
Lime & Shale.....3765 Ft.
Granite.....3766 Ft. TD

RECEIVED
STATE CORPORATION COMMISSION
1-3-63
JAN 3 1963

CONSERVATION DIVISION
Wichita, Kansas

State of Kansas)
Decatur County) SS

I hereby certify that the foregoing is, to the best of my knowledge and belief, a true and correct drilling log as shown by the drilling reports in connection with the aforesaid well.

W. W. Sausage
W. W. Sausage

Subscribes and sworn to before me, the undersigned, a Notary Public, this 2 of January 1962.

E. L. Smith

My commission expires October, 1966