

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20123-00-00

RECEIVED
STATE CORPORATION COMMISSION
OCT 6 1969
CONSERVATION DIVISION
Wichita, Kansas
10-6-1969

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name A. L. Abercrombie, Incorporated,

Complete Address 801 Union Center Building, Wichita, Kansas.

Lease Name Powell Well No. 1

Location NE-NE Sec. 24 Twp. 1 Rge. (E) (W) 27

County Decatur Total Depth 3538'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 8:15 AM Day 1 Month 10 Year 1969

The above well was plugged as follows:

243'--8 5/8" Surface casing, cement circulated with 175 Sx. (6 3/4" Hole).
Top of Dakota section @ 985'.

Circulated hole with heavy mud. Pulled DP to 1210' and displaced 65 Sx. cement thru
DP from 1210' to 885'. Pulled DP to 275' and displaced 15 Sx. cement thru DP from
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/6/69
INV. NO. 588-U

Signed: W. L. Nichols
Well Plugging Supervisor