

**KANSAS
STATE CORPORATION COMMISSION**

CONSERVATION DIVISION AGENT'S REPORT

15-039-20089-00-00

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAY 9 1969
CONSERVATION DIVISION
Wichita, Kansas
5-9-1969

Operator's Full Name William D. Hewit,

Complete Address: 980 Denver Club Building, Denver, Colorado. 80202

Lease Name Adda Welch Well No. 1

Location CNE-SW Sec. 17 Twp. 1 Rge. (E) (W) 27

County Decatur Total Depth 3701

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: L. J. Dreiling & Sons, Incorporated,

Address: R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 1:00 PM Day 5 Month 5 Year 1969

The Above well was plugged as follows:

219'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1150'.

Circulated hole with heavy mud. Pulled DP to 1380' and displaced 100 Sx. cement
thru DP from 1380' to 1055'. Pulled DP to 240' and displaced 20 Sx. cement thru DP
from 240' to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/9/69

INV. NO. 1537-4

Signed: M. B. Dreiling
Well Plugging Supervisor