

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-039-20290-00-00

RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1974
11-15-1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name John O. Farmer, Incorporated,

Complete Address 370 West Wichita Avenue, Russell, Kansas.

Lease Name Huff 'B' Well No. 3-1

Location SW-SE-SW Sec. 15 Twp. 1 Rge. (E) (W) 27

County Decatur Total Depth 3577'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 8:00 PM Day 5 Month 11 Year 1974

The above well was plugged as follows:

212'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 110 Cu. Ft. cement
thru DP from 1250' to 925'. Pulled DP to 225' and displaced 30 Cu. Ft. cement thru
DP from 225' to 150'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 11/15/74
INV. NO. 303-W

Signed: W. L. Nichols
Well Plugging Supervisor