

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20158-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAY 4 1970
CONSERVATION DIVISION
Wichita, Kansas
5-4-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Donald C. Slawson, Incorporated.

Complete Address 408 One-Twenty Building, Wichita, Kansas.

Lease Name Cathcart Well No. C-1

Location CNE-NE Sec. 32 Twp. 1 Rge. (E) (W) 27

County Decatur Total Depth 2080'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Slawson Drilling Company, Incorporated.

Address 408 One-Twenty Bldg., Wichita, Kas. License No.

Operation Completed: Hour 4:00 AM Day 29 Month 4 Year 1970

The above well was plugged as follows:

319'--8 5/8" Surface casing, cement circulated with 295 Sx.
Top of Dakota section @ 1050'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 100 Sx. cement thru
DP from 1250' to 925'. Pulled DP to 340' and displaced 25 Sx. cement thru DP from
340' to 265'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 5/4/70
INV. NO. 1839-44