

15-039-20102-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

*SP*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED  
STATE CORPORATION COMMISSION

AUG 14 1969  
CONSERVATION DIVISION  
Wichita, Kansas

8-14-1969

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Okmar Oil Company,  
Complete Address 1130 Wichita Plaza Building, Wichita, Kansas.  
Lease Name Metcalf Well No. 1  
Location N/2-N/2-SW Sec. 28 Twp. 1 Rge. (E) (W) 27  
County Decatur Total Depth 2327'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor L. J. Dreiling & Sons, Incorporated,  
Address Victoria, Kansas. License No.         
Operation Completed: Hour 11:00 PM Day 8 Month 8 Year 1969

The above well was plugged as follows:

210'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 1035'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 100 Sx. cement thru  
DP from 1250' to 925'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from  
240' to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. S. Nichols*  
Well Plugging Supervisor

DATE 8/14/69  
INV. NO. 290-W