

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
7-19-1976
JUL 19 1976

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -039 -20,347-00-00 (of this well)

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name S & W Drilling Co., Inc.

Complete Address Box 132, Oberlin, Kansas

Lease Name Metcalf Well No. 1

Location C SE SE Sec. 28 Twp. 1 Rge. (E) (W) 27

County ~~Osage~~ Decatur Total Depth 3312'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Rains & Williamson

Address Wichita, Kansas License No.

Operation Completed: Hour 8:30 A Day 15 Month 7 Year 1976

The above well was plugged as follows:

RTD 3312' 8 5/8 csg set 204' cwc 150 sx. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 900' thru drill pipe.

Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/29/76
INV. NO. 3526-11

Signed: Leo Massey
Well Plugging Supervisor