

State of Kansas



15-039-20290-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 15 1974

11-15-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sam Farmer of John O. Farmer, Incorporated has this date requested permission to plug the following described well:

Mr. Farmer guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: 370 W. Wichita Ave., Russell, Kansas.

Lease Name: Huff Well No. B-1

Location: SW-SE-SW Sec. 15 Twp. 1 Rge. (E)(W) 27

County: Decatur Total Depth 3577' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Farmer was instructed to plug the well as follows:

212'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1025'.

Circulate hole with heavy mud. Pull DP to 1250' and displace 110 Cu. Ft. cement thru DP. Pull DP to 225' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

K. L. Nichols

Conservation Division Agent