



15-039-20587-00-00

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

Dear Sir:

Mr. Jawby Herman of Thunderbird Drilling Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Thunderbird Drilling Inc.  
Complete Address: 7701 East Kellogg # 780 #18407 Wichita, Mo  
Lease Name: Stuff Well No. #-#1  
Location: NW-NW-NE Sec. 15 Twp. 1<sup>S</sup> Rge. 27<sup>W</sup> (E) (W)  
County: Decatur Total Depth: 3470 FE  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Herman was instructed to plug the well as follows:

8 5/8" 264 FE SP. CUC w/200 # Common - 2% Gel - 3% CaCl.  
Order 115 # 50/50 Pozmix 4% Gel - 3% CaCl. + 8 5/8" Plug  
spot with Drill Stem - with heavy mud between all plugs  
1<sup>st</sup> Plug @ 1160 FE w/60 # Cmt.  
2<sup>nd</sup> Plug @ 300 FE w/40 # Cmt  
3<sup>rd</sup> Plug - Solid Bridge @ 40 FE to 0 w/10 # Cmt  
5<sup>th</sup> In Ret Hole

Very truly yours,

(By Marion Schmidt)  
STATE CORPORATION COMMISSION  
RECEIVED  
JUN 25 1981

Marion Schmidt  
Conservation Division Agent  
Wichita, Kansas  
6-25-1981