



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Bernie Meyer of Murfin Drilling Co has this date requested permission to plug the following described well:

Operator's Full Name: Cinco Exploration % Melvin Hutzman

Complete Address: P.O. Box 3723 - Victoria, Texas.

Lease Name: B. H. Metcalf Well No. #1

Location: SE - SE Sec. 34 Twp. 1^S Rge. 27 (W)

County: Decatur Total Depth: 3851 FT

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Meyer was instructed to plug the well as follows:

- 8 5/8" 262 FT 50' CUC w/200ST Cement - 2% Gel - 3% Ca-Cl
- Order 105ST 50' Pozmix 6% Gel + 8 5/8" Plug - Elev. 2612^{KS}
- spot with Drill Stem - with Heavy Mud between all Plugs.
- 1ST Plug @ 1200 FT w/60ST Cmt.
- 2ND Plug @ 240 FT w/25ST Cmt.
- 3RD Plug - Solid Bridge - Pulls - Plug @ 40 FT to 0 w/10ST Cmt.
- 5TH In Rat Hole

Very truly yours, By [Signature] RECEIVED CONSERVATION DIVISION

[Signature]
Conservation Division Agent
DEC - 1 1980
CONSERVATION DIVISION
Wichita, Kansas

12-1-1980