

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-039-20494-00-01
LEASE NAME Huff

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1
_____ Ft. from S Section Line
_____ Ft. from E Section Line

LEASE OPERATOR C. Dale Stromquist
ADDRESS P.O. Box 1054 Liberal, Ks. 67905
PHONE#(316) 624-3902 OPERATORS LICENSE NO. 8294

SEC. 9 TWP. 1 RGE. 26 (E) or (W)
COUNTY Decatur

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed _____
Plugging Commenced 3-13-96
Plugging Completed 3-28-96

The plugging proposal was approved on _____ (date)
by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3630'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	289'	none
				4 1/2'	3622'	405'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each section. Plugged off bottom with sand to 3201', dumped 4 sacks cement. Shot pipe at 1801', and @ 1319', pumped 50 sacks cement with 300# hulls, displaced to 800'. Shot pipe at 750' and 405', circulated to surface with 75 sacks cement w/ 100# hulls, pulled pipe. (60/40 POZMIX 10% gel) Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: C. Dale Stromquist Liberal, Ks.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 209 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 2nd day of April, 19 96

[Signature]
Notary Public

My Commission Expires:

