

RECEIVED

JAN 22 2004

KCC WICHITA

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-015-30350-00-01 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date ** Completed (01/20/66)

12/04

Well Operator: Northstar Investments, Inc. (Owner / Company Name) KCC License #: 30601 (Operator's)

Address: 13735 Pinnacle Drive City: Wichita

State: Kansas Zip Code: 67230 Contact Phone: (316) 733-8996

Lease: Liggett Well #: W-1 Sec. 16 Twp. 26s S. R. 8 East West

NE NW NW Spot Location / QQQQ County: Butler

400' Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1190' Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # E-23,006 Other: _____

Conductor Casing Size: None Set at: N/A Cemented with: N/A Sacks _____

Surface Casing Size: 8 5/8" Set at: 120' Cemented with: 78 Sacks _____

Production Casing Size: 4 1/2" Set at: 2605' Cemented with: 150 Sacks _____

List (ALL) Perforations and Bridgeplug Sets: 2464' - 2483'

Elevation: 1425' (G.L. / K.B.) T.D.: 2605' PBTD: 2605' Anhydrite Depth: Unknown (Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Tie on to parted tubing @ 552' with an overshot and pack-off insert. Establish injection down tubing, and cement with 10 sxs (displacing to 50' above perforations). The well will then be perforated @ 500' and cement circulated to surface, inside and outside of the casing. Casing will then be cut off at surface.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Sam's Well Service

P.O. Box #2444 - Ponca City, OK (Billing Address) Phone: (620) 221-3324

Address: P.O. Box #2444 - (Billing Address) City / State: Ponca City, OK 74602

Plugging Contractor: United Cementing (Company Name) KCC License #: 30437 (Contractor's)

Address: 2510 West 6th Street - Eldorado, KS 67042 Phone: (316) 321-4680

Proposed Date and Hour of Plugging (if known?): 01/21/04 (10:30 a.m.)

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 01/20/04 Authorized Operator / Agent: [Signature] (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

9/04

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Northstar Investments, Inc.
13735 Pinnacle
Wichita, KS 67230-1545

January 28, 2004

Re: LIGGETT #W1
API 15-015-30350-00-01
NENWNW 16-26S-8E, 400 FNL 1190 FWL
BUTLER COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely

David P. Williams
Production Supervisor

District: #2
130 S. Market, Room 2125
Wichita, KS 67202-3208
(316) 337-6231