



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
04-03-1972
APR 3 - 1972
CONSERVATION DIVISION
Wichita, Kansas

15-039-20228-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dale Bucheister of John O. Farmer, Incorporated has this date requested permission to plug the following described well:

Mr. Bucheister guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: 370 West Wichita Avenue, Russell, Kansas.

Lease Name: Walters Well No. 2

Location: NW-SW Sec. 4 Twp. 1 Rge. (E)(W) 27

County: Decatur Total Depth 3500' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bucheister was instructed to plug the well as follows:

240'--8 5/8" Surface casing, cement circulated .
Top of Dakota section @ 975'.

Circulate hole with heavy mud. Pull DP to 1200' and displace 110 Cu. Ft. cement thru DP. Pull DP to 275' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,


Conservation Division Agent