



ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

20051  
15-039-~~20038~~-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 9 09 - 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Dale Oller of Murfin Drilling Company, has this

date requested permission to plug the following described well:

Mr. Oller guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: 370 West Wichita, Russell, Kansas.

Lease Name: Bremer Well No. 1

Location: CN/2-NE/4 Sec. 4 Twp. 1 Rge. (E)(W) 27

County: Decatur Total Depth 3395 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Oller was instructed to plug the well as follows:

275'--8 5/8" Surface casing, cement circulated with 250 Sx.  
Top of Dakota Section @ 1100'.

Circulate hole with heavy mud. Pull DP to 1310' and displace 100 Sx.  
cement thru DP. Pull DP to 305' and displace 25 Sx. cement thru DP. Pull  
DP. set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

*A. L. Nichols*  
Conservation Division Agent