

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21153-00-00
Spot: SWNESW Sec/Twnshp/Rge: 20-8S-19W
1650 feet from S Section Line, 3630 feet from E Section Line
Lease Name: LOWRY B Well #: 2
County: ROOKS Total Vertical Depth: 3422 feet

Operator License No.: 31725
Op Name: SHELBY RESOURCES LLC
Address: 5893 SADDLE CREEK TRAIL
PARKER, CO 80134

PROD Size: 4.5 feet: 3420
SURF Size: 8.625 feet: 305

11122

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/05/2004 10:30 AM

Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS

Proposal Rcvd. from: BRIAN KARLIN Company: SHELBY RESOURCES' LLC Phone: (785) 623-3194

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 500# hulls.
Fluid level at surface.
Squeeze job 1050' w/250 sxs and 2648'-2680' w/150 sxs.

Plugging Proposal Received By: HERB DEINES
Date/Time Plugging Completed: 04/05/2004 1:00 PM

WitnessType: COMPLETE (100%)
KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

M.I.R.U. Ran tubing to 2000'.
Allied pumped 120 sxs 60/40 pozmix - 10% gel with 200# hulls. Circulated cement.
PTOH. Allied pumped 80 sxs cement with 300# hulls.
Max. P.S.I. 900#. S.I.P. 300#.
Hooked up to backside instant 700#.

RECEIVED
APR 08 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

RD

Signed

Richard Williams

(TECHNICIAN)

INVOICED


48-04

2004061404

APR 06 2004

INDEXED
 10/18/86

EAGLE PETROLEUM CORPORATION REPLACEMENT CARD
 120 S. HOLLAND, #501 #2 LOWRY 20-8-19W
 WICHITA, KS. 67209 SW NE SW
 CONTR MONTGOMERY DRILLING CTY ROOKS
 GEOL DON F. MOORE FIELD BRAY
 ELV 1976 KB SPD 10/24/80 CARD ISSUED 9/10/81 IP P 10 BOPD, NW
 API 15-163-21,153 LKC 3230-3232



LOG	Tops	Depth/Datum	
LANS	3166	1190	8 5/8 " 305, 4 1/2 " 3420 ..
BKC	3375	1399	NO CORES
CONG	3390	1414	DST (1) 3190-3214 (LKC) / TIMES NA, REC 3' M, PRESSURES NA
ARB	3415	1439	DST (2) 3215-3238 (LKC) / 45-45-45, 60' GIP, REC 150' GCO
RTD	3422	1446	(85% OIL), SIP 671#, FP 43-43 / 43-43#
			DST (3) 3335-3360 (LKC) / TIMES NA, REC 5' M, PRESSURES NA
			MICT - CO, PF (LKC) 3230-3232, AC 1000 GAL, SO, POP, P 10
			BOPD, NW

INFO RELEASED: 9/18/86 - ADDED WELL INFO
 NOTE: INFO RELEASED: 1/7/82 - WAS OIL WELL - TIGHT HOLE