

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-04907-00-00
Spot: E2SENE Sec/Twnshp/Rge: 34-11S-17W
3362 feet from S Section Line, 287 feet from E Section Line
Lease Name: DREILING Well #: 2
County: ELLIS Total Vertical Depth: 3468 feet

Operator License No.: 6622
Op Name: SCHOENBERGER, J.L. D/B/A JASON OIL
Address: PO BOX 701 363 W 12TH ST
RUSSELL, KS 67665

PROD Size: 5.5 feet: 3461
SURF Size: 10.75 feet: 0

11/12⁷¹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/07/2004 11:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: JIM SCHOENBERGER Company: JASON OIL COMPANY Phone: (785) 483-4204

Proposed Plugging Method: Emergency plug with rig over the hole.
Ordered 325 sxs 60/40 pozmix - 10% gel - 800# hulls.
Holes in the casing at 1800' - 1900'. Squeeze at 900'.
4 sets of perfs open.
Dakota 359'-659'. Anhy. 1185'-1215'. Salt 1532'-1717'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/07/2004 2:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

RIH with tubing to 2040'.
Tied onto tubing and pumped 160 sxs 60/40 pozmix with 600# hulls mixed in. No returns.
Pulled tubing to 1210' - pumped 80 sxs cement with 200# hulls mixed in. No returns.
Pulled tubing to 750' - pumped 50 sxs 60/40 pozmix - cement circulated.
Topped 5 1/2" with 20 sxs cement. 5 1/2" was standing full.
Dug out backside and cut off hanger to fill backside.
10 3/4" took 15 sxs cement to fill to surface.
Hole standing full of cement.

RECEIVED
APR 12 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #17009.

Plugged through: TBG

District: 04

Signed: *Pat Staab*

(TECHNICIAN)

INVOICED

DATE

4-13-04

INV. NO.

2004061412

Form CP-2/3

APR 08 2004

EARL WAKEFIELD

#2 DREILING

34-11-17W
CEL SE NE

Contr

ELLIS County

E 1989

Comm. 2-24-43

Comp. 4-14-43

IP

1340 BOPD

ECHO

Tops	Depth	Datum
ANH	1185	+804
ARB	3459	-1470
TD	3468	

Casing
5" 3461

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

13910 W.M.
2742