

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20307-00-00
Spot: NWNE Sec/Twnshp/Rge: 22-32S-33W
660 feet from N Section Line, 1980 feet from E Section Line
Lease Name: LEMERT BETTY Well #: 1
County: SEWARD Total Vertical Depth: 6011 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: PO BOX 18496 6200 N WESTERN AVE.
OKLAHOMA CITY, OK 73154

PROD Size: 5.5 feet: 6010 WITH 350 SX CMT
SURF Size: 8.625 feet: 1600 WITH 800 SX CMT

\$ 195³⁶

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/24/2004 9:00 AM

Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (405) 848-8000

Proposed Plugging Method: PUMP 300# HULLS & 25 SX CMT. PRESSURE TEST. PERFORATE & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEVIN STRUBE

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 03/24/2004 2:00 PM

KCC Agent: JIM HOLLAND

Actual Plugging Report:

PUMP 300# HULLS WITH 25 SX CMT. DISPLACE TO BOTTOM WITH 130 BBL MUD. PRESSURE TO 500 PSIG & SHUT IN. RUN IN HOLE TO 1600' & PERFORATE. ESTABLISH CIRCULATION & PUMP 400 SX CMT TO FILL 5 1/2" & 5 1/2" X 8 5/8" ANNULUS FROM 1600' TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
5654	5774		
4784	4920		

RECEIVED
APR 08 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Jim Holland (TECHNICIAN) JA

INVOICED
DATE 4-8-04
INV. NO. 2004061399