

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22810-00-01
Spot: SWSWNE Sec/Twnshp/Rge: 11-14S-18W
2970 feet from S Section Line, 2210 feet from E Section Line
Lease Name: EMMA LEIKER Well #: 2
County: ELLIS Total Vertical Depth: 3675 feet

Operator License No.: 32811
Op Name: OSAGE RESOURCES, LLC
Address: 1605 E. 56TH AVENUE
HUTCHINSON, KS 67502

PROD Size: 4.5 feet: 3668 200 SX CMT
SURF Size: 8.625 feet: 1192 475 SX CMT

11944

Well Type: EOR UIC Docket No: E26264.3 Date/Time to Plug: 03/30/2004 12:00 PM

Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: RON DAVIS Company: OSAGE RESOURCES, LLC Phone: (620) 664-9622

Proposed Plugging Method: Ordered out 220 sxs 60/40 pozmix - 10% gel - 300# hulls.
Well squeezed at 1410' w/250 sxs cement.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/30/2004 2:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Swaged onto 4 1/2" - mixed and pumped 190 sxs cement with 200# hulls.
Max. P.S.I. 1000#. S.I.P. 400#.
Filled annulus up with 70 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3240	3350		

RECEIVED
APR 08 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

170

Signed

Jay Pfeifer

(TECHNICIAN)

INVOICED

DATE

4-8-04

INV. NO.

2004061402

APR 05 2004

11-14-18W
 #2 EMMA LEIKER
 100'E, SW SW NE

MIDWAY DRILLING INC
 P.O. BOX 1325
 GREAT BEND, KS 67530
 CONTR ABERCROMBIE DRILLING CTY ELLIS
 GEOL _____ FIELD BURNHAM EXT (1/8 N)
 E 1984 KB CM 1/19/82 CARD ISSUED 4/1/82 IP P 30 BOPD, TR W
 1979 GL _____ LKC 3436-40
 API 15-051-22,810

	+	+
	+	+

SMP	TOPS	DEPTH	DATUM
TOP		2944	- 960
HEEB		3215	-1231
TOR		3233	-1249
LKC		3259	-1275
BKC		3492	-1508
MARM		3499	-1515
CONG		3517	-1533
ERO ARB		3533	-1549
ARB		3544	-1560
RTD		3675	-1691

8-5/8" 1192; 4 1/2" 3668
 NO DST'S
 MICT - CO, PF (LKC) 16/3436-40, AC
 500G (HCL), SWB LD W/GSO, POP, P 30
 BOPD, TR W, 3/21/82

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

INFO RELEASED: 5/20/82
 WAS OIL WELL-