

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21511-00-00
Spot: W2NWSW Sec/Twnshp/Rge: 30-30S-18W
2200 feet from S Section Line, 4840 feet from E Section Line
Lease Name: LOLA Well #: 1
County: KIOWA Total Vertical Depth: 5200 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS, INC. OF KANSAS
Address: PO BOX 8647
WICHITA, KS 67208

PROD Size: 4.5 feet: 5196 WITH 140 SX CMT
SURF Size: 8.625 feet: 651 WITH 150 SX CMT

129.00

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/06/2004 2:10 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 4840' & 4 SX CMT. PLUG AT 1050' WITH 50 SX CMT. PLUG AT 675' WITH 50 SX CMT. PLUG AT 0-40' WITH 10 SX CMT. USE 10 SX GEL FOR SPACER.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/06/2004 3:15 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

PBTD 4960'. SAND BACK TO 4840' WITH 4 SX CMT. 1ST PLUG PUMP 15 SX GEL & 50 SX CMT AT 1050'. 2ND PLUG PUMP 50 SX CMT AT 675'. 3RD PLUG PUMP 10 SX CMT AT 0-40'. HOLE FULL AT END OF JOB.

Perfs:

Top	Bot	Thru	Comments
5096	5106		SPF
5072	5088		SPF
4898	4906		SPF

RECEIVED
APR 08 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3740' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
APR - 7 2004
KCC Dodge City

Signed _____

Scott Alberg
(TECHNICIAN)
INVOICED
DATE 4-8-04
NO. 2004061401