

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-20100-00-01
Spot: S2SESW Sec/Twnshp/Rge: 13-23S-15W
330 feet from S Section Line, 1900 feet from W Section Line
Lease Name: TRANBARGER Well #: 1
County: PAWNEE Total Vertical Depth: 4200 feet

Operator License No.: 8045
Op Name: C & B OPERATING INC.
Address: PO BOX 65
ST. JOHN, KS 67576

PROD Size: 5.5 feet: 4090
SURF Size: 8.625 feet: 282 WITH 225 SX CMT

\$ 136⁵⁰

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/31/2004 1:30 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND BACK TO 3940' WITH 2 SX CMT. PLUG AT 1050' WITH 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG
Date/Time Plugging Completed: 03/31/2004 4:03 PM

Witness Type: COMPLETE (100%)
KCC Agent: RICHARD LACEY

Actual Plugging Report:


Perfs:

SANDED TO 3730' & 4 SX CMT WITH DUMP BAILER. PUMPED PLUGS THROUGH CASING. 1ST PLUG AT 1050' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2131' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

INVOICED

DATE

4-9-04

INV. NO.

2004061407