

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-04940-00-00
Spot: S2SWNW Sec/Twnshp/Rge: 11-11S-18W
2970 feet from S Section Line, 4620 feet from E Section Line
Lease Name: CARMICHAEL Well #: 1
County: ELLIS Total Vertical Depth: 3425 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

PROD Size: 5.5 feet: 3424 125 SX CMT
SURF Size: 8.625 feet: 1180 300 SX CMT

111 31

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/30/2004 10:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: STAN FROETSCHNER Company: MURFIN DRILLING CO., INC. Phone: (785) 483-5371

Proposed
Plugging
Method:

Ordered 375 sxs cement with 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/30/2004 1:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

RIH with tubing to 3400' - pumped 100 sxs cement with 300# hulls.
Pulled tubing to 1700' - circulated with 165 sxs cement with 200# hulls - thru casing and annulus.
Pulled all tubing and topped off with 25 sxs cement.
Total of 290 sxs 60/40 pozmix and 500# hulls.

Perfs:

Top	Bot	Thru	Comments
3424	3425		
3404	3406		
3378	3382		

RECEIVED
APR 12 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY, STEWART TANK-WATER.

Plugged through: TBG

District: 04

Signed

Roger Moses

(TECHNICIAN)

INVOICED

DATE

4-13-04

INV. NO.

2004062411

Form CP-2/3

APR 05 2004