

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-10238-00-00
Spot: NW Sec/Twnshp/Rge: 25-34S-42W
3960 feet from S Section Line, 3960 feet from E Section Line
Lease Name: BROWN F Well #: 1
County: MORTON Total Vertical Depth: 3210 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: PO BOX 27570 5 E GREENWAY PLZ
HOUSTON, TX 77227

CIBP Size: feet: 2918
PROD Size: 5.5 feet: 3198 WITH 275 SX CMT
SURF Size: 8.625 feet: 601 WITH 400 SX CMT #104 33

Well Type: GAS UIC Docket No: Date/Time to Plug: 04/02/2004 10:00 AM

Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: JOHN Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PLUG AT 1300' WITH 40 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 300' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND
Date/Time Plugging Completed: 04/02/2004 4:00 PM

Witness Type: COMPLETE (100%)
KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 3165'. CIBP SET @ 2918', NO FLUID IN HOLE. PUMP 41 BBL MUD TO 1300', CHECK WITH WIRELINE. PUMP 25 SX CMT INSIDE 5 1/2" @ 1300'. DISPLACE WITH MUD. PRESSURE TO 500 PSIG. PULL OUT OF HOLE TO 600'. CIRCULATE HOLE & PUMP 40 SX CMT. GOOD CIRCULATION. PULL OUT OF HOLE TO 300'. LOAD HOLE & PUMP 30 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
3120	3135		
3100	3112		
3042	3052		

RECEIVED
APR 14 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 830' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland PART A
INVOICE (TECHNICIAN)

DATE 4-14-04
INV. NO. 2004061413

Form CP-2/B