

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-039-20325-00-00

LEASE NAME Ival E. Kathka

WELL NUMBER #1

2970 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 7 TWP. 1 RGE. 28 (E) or (W)

COUNTY Decatur

Date Well Completed 3-19-76

Plugging Commenced 7-16-03

Plugging Completed 7-16-03

RECEIVED

JUL 18 2003

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Coas. Div.
office within 30 days.

LEASE OPERATOR Helberg Oil Company

ADDRESS P. O. Box 32 Morland, Kansas 67650

PHONE (785) 627-5665 OPERATORS LICENSE NO. 5669

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-3-03 (date)

by Hays office (Plugging agent was Darrel Dipman) (KCC District Agent's Name).

Is ACO-1 filed? Yes if not, is well log attached? _____

Producing Formation L-KC Depth to Top 3539 Bottom N/A T.D. 3840

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface Pipe		0	211	85/8	211	0
Production Casing		0	3806	4 1/2	3806	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Plugged casing with 165 sacks 60-40 poz mix 10% gel with 300# hulls. Pressured to 700# and shut in at 300#. Cemented between surface pipe and casing with 60 sacks 60-40 Poz mix 10% gel and 100# hulls. Pressured to 100# and shut in at 100#.

Name of Plugging Contractor Allied Cementing Co., Inc. License No. _____

Address P. O. Box 27 Oakley, Kansas 67748

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Jerry M. Helberg

STATE OF Kansas COUNTY OF Graham, ss.

Jerry M. Helberg

(~~Employee of Operator~~) or (Operator) of


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Jerry M. Helberg

(Address) P. O. Box 32 Morland, Ks 67650

SUBSCRIBED AND SWORN TO before me this 17th day of July, 2003, 19

My Commission Expires: _____



Notary Public