


15-039-00172-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Decatur County. Sec. 23 Twp. 1S Rge. 28 (E) W (W)
Location as "NE/CNW/SW" or footage from lines. NW NW SW
Lease Owner Great Basins Petroleum Company
Lease Name Commercial Bank of Nelson Well No. 1
Office Address 1515 Mile High Center, Denver 2, Colorado
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 19, 19 57
Application for plugging filed May 19, 19 57
Application for plugging approved May 19, 19 57
Plugging commenced May 19, 19 57
Plugging completed May 19, 19 57
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4063 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	315	8 5/8"	315	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

From 4063' to 310' - heavy rotary mud and plug
310' to 248' - 1/2 sack hulls, 20 sacks cement
248' to 40' - heavy rotary mud and plug
40' to 6' - 1/2 sack hulls, 10 sacks cement
6' to surface - cellar

RECEIVED
STATE CORPORATION COMMISSION
MAY 22 1957
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Peel Brothers, Inc. 5-22-1957
Address P.O. Box 88, Hoisington, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Peel Brothers, Inc. (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. PEEL BROTHERS, INC.

(Signature) By: Al H. Smith
P.O. Box 88, Hoisington, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of May, 19 57

My commission expires April 27, 1960 Ruth Brant Notary Public.

PLUGGING
FILE SEC 23 T. 1 R. 28
BOOK PAGE 14 LINE 32

15-039-00172-00-00

DRILLERS' LOG

Company: Great Basins Petroleum Company

NW NW SW
Sec. 23, Twp. 1S, Rge. 28W,

Farm Name: Commercial Bank of Nelson Well No. 1

County: Decatur,
Kansas

Total Depth: 4063'

Comm: 5/8/57 Comp: 5/19/57
Contractor: Peel Brothers, Inc.

Elevation:

Production: Dry

Casing: 8 5/8" @ 315' cem.

Figures below indicate bottoms of formations:

Clay and sand	0 -	220
Shale		1100
Sand and shale		1350
Shale		1420
Sand and shale		1500
Shale and shells		1720
Shale		1850
Anhydrite		1865
Red bed and anhydrite streaks		2035
Red bed and shale		2230
Anhydrite		2255
Shale		2740
Shale and lime		2975
Shale		3075
Shale and lime		3540
Lime		3725
Lime and shale		3900
Granite wash		3954
Weathered granite		4063
Total Depth		4063

This is to certify that the above information is to the best of our knowledge, true and correct.

PEEL BROTHERS, INC.

BY: Al H. Smith

SUBSCRIBED AND SWORN to before me this 21st day of May, 1957

My commission expires: April 27, 1960

Rich Brack
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
5-22-1957
MAY 22 1957
CONSERVATION DIVISION
WICHITA, KANSAS

PLUGGING
FILE SEC 23 T 1 R 28W
BOOK PAGE 14 LINE 32