

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-039-20353-00-00
Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Decatur

County, Sec. 8 Twp. 1S Rge. 28 ~~K29X~~ (W)

Location as "NE/CNW/SW" or footage from lines. C NE NW

Lease Owner S & W Drilling Co., Inc.

Lease Name Dowling #2 Well No. #4

Office Address Box 132, Oberlin, Kansas 67749

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 8-29-76 19

Application for plugging filed 8-29-76 19

Application for plugging approved 8-29-76 19

Plugging commenced 8-29-76 19

Plugging completed 8-29-76 19

Reason for abandonment of well or producing formation Commercial quantities of oil not found.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor, Palco, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3742 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	247'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug @ 1300' w/70 sx.

Plug @ 200' w/20 sx.

Plug @ 40' w/10 sx.

RECEIVED
STATE CORPORATION COMMISSION

SEP 02 1976

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Rains & Williamson Oil Co., Inc. 9-2-1976
Address 435 Page Court, 220 W. Douglas, Wichita, Kansas 67202


STATE OF Kansas COUNTY OF Sedgwick
Wilson Rains, President of Rains & Williamson Oil Co., Inc.

(employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
435 Page Court, 220 W. Douglas, Wichita, Ks
(Address)

Subscribed and Sworn to before me this 31 day of August 19 76

My commission expires 10-4-79



Juanita M. Green
Notary Public.

WELL LOG

15-039-20353-00-00

COMPANY S & W Drilling Co., Inc.

SEC. 8 T. 1S R. 28W
LOC. C NE NW

FARM Dowling NO. #2

RIG. NO. #4


TOTAL DEPTH 3742'

COUNTY Decatur
KANSAS

COMM. 8-23-76

COMP. 8-29-76

CONTRACTOR Rains & Williamson Oil Co., Inc.



CASING

20 10
15 8
12 6
13 5

5/8" @ 247' w/ 160 sx. 60/40 pos.
2% gel, 3% cc.

ELEVATION

PRODUCTION

D&A

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale & Shells	94
Sand	178
Shale	257
Shale & Sand	450
Shale	1220
Sand	1290
Shale & Sand	1890
Shale & Redbed	2225
Redbed & Shale	2277
Shale & Redbed	2850
Redbed & Shale	3045
Shale	3145
Shale & Lime	3530
Core	3544
Lime	3742
<u>Rotary Total Depth</u>	<u>3742</u>

RECEIVED
STATE CORPORATION COMMISSION

SEP 02 1976

9-2-1976

CONSERVATION DIVISION
Wichita, Kansas

State of Kansas

County of Sedgwick

ss:

I, Wilson Rains, President of the Rains & Williamson Oil Co., Inc. Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Dowling #2 well.

Wilson Rains
Wilson Rains

Subscribed and sworn to before me this 31 day of August 1976

My Commission Expires: 10-4-79

Juanita M. Green
NOTARY PUBLIC
Juanita M. Green

