

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form CP-1
September 2003
Form must be Typed
Form must be Signed
All blanks must be Filled

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

15-129-10503-00-01

API # 15- 129-85029 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued.

Indicate original spud or completion date 7/30/56

Well Operator: Anadarko Petroleum Corporation KCC License #: 4549
(Owner/Company Name) (Operator's)

Address: 1201 Lake Robbins Drive City: The Woodlands

State: TX Zip Code: 77380 Contact Phone: 832 636-3128

Lease: Interstate Unit Well #: 30 Sec. 31 Twp. 34 S R. 43 East West

CNW NW Spot Location/QQQQ County Morton

660 Feet from (in exact footage) North / South (from nearest outside section corner) Line of Section (not Lease Line)

660 Feet from (in exact footage) East / West (from nearest outside section corner) Line of Section (not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # 21,363 Other _____

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 09 2004
CONSERVATION DIVISION
WICHITA, KS

Conductor Casing Size: 12-1/2" Set at: 97' Cemented with: N/A Sacks

Surface Casing Size: 8-5/8" Set at: 1143' Cemented with: 750 Sacks

Production Casing Size: 4-1/2" Set at: 4230' Cemented with: 500 Sacks

List (ALL) Perforations and Bridgeplug Sets: 4136'-4143' CTBP 4145'

Elevation: 3478 (G.L. K.B.) T.D. 4265' PBSD 4145' Anhydrite Depth _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Pump 2 sxs hulls and 26 sxs Class H cement from 4080' to 3780'. Cut and pull 4-1/2" casing at 1300'. Pump 35 sxs Class H cement from 1300' to 950'. Plug with cement from 150' to 4'. Cut off and cap 8-5/8" 4' below GL and cap well with 1/4" steel cap.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Logs were submitted with ACO-1

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

List Name of Company Representative authorized to be in charge of plugging operations:
Darrel W. Smith Phone: 620 697-3619

Address: 1106 Sherman Ave. City/State Elkhart, KS 67950

Plugging Contractor Sargent & Horton Plugging, Inc. KCC License # 31151
(Company Name) (Contractor's)

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731 Phone: 405 854-6515

Proposed Date and Hour of Plugging (If known?): 2-11-04 @ 9:30 AM plugged

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 2-6-04 Authorized Operator / Agent: Jerry N. Blossom
(Signature)

/Jerry N. Blossom