


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

15-039-00485-00-00

NORTH



Locate well correctly on above
Section Plat

DECATUR County. Sec. 1 Twp. 1 Rge. 27 (E) W-(W)
Location as "NE/CNW/SW" or footage from lines SW SW NW
Lease Owner D. G. Hansen
Lease Name Sater Well No. 1
Office Address Logan, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) m Dry Hole
Date well completed November 3 19 56
Application for plugging filed November 3 19 56
Application for plugging approved November 3 19 56
Plugging commenced November 4 19 56
Plugging completed November 4 19 56
Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3617 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 346' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 300'.
Set plug. Put in 15 sacks cement and 1/2 sack Hulls. Filled with heavy mud up to 40'. Set plug. Filled to top with 10 sacks cement and 1/2 sack Hulls.

RECEIVED
STATE CORPORATION COMMISSION
11-10-1956
NOV 10 1956
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G DRILLING CO.
Address 107 Rule Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jay H. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jay H. Galloway
107 Rule Building
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of November, 1956

My commission expires May 20, 1959

Vicky Jacobs
Notary Public.

PLUGGING
FILE SEC 1 T 1 R 27w
BOOK PAGE 113 LINE 8

15-039-00485-00-00
CONTRACTOR'S WELL LOG

OPERATOR D. G. HANSEN WELL NAME SATER #1
 LOCATION SW SW NW SECTION 1-1-27W RIG NO. 1
 COUNTY DECATUR STATE KANSAS
 COMMENCEMENT DATE OCTOBER 26, 1956 COMPLETION DATE NOVEMBER 4, 1956

LOG OF WELL

Elevation 2566' rotary bushing
 All measurements from the top of rotary bushing.

| FROM | TO | FORMATION | DEVIATION FROM VERTICAL | REMARKS |
|------|------|-------------------|-------------------------|----------------|
| 0 | 200 | Surface Clay-Sand | | |
| 200 | 260 | Sand-Shells | | |
| 260 | 625 | Shale-Sand | | |
| 625 | 710 | Sand | | |
| 710 | 1120 | Sand-Shale | | |
| 1120 | 1550 | Sand-Shale | | |
| 1550 | 1740 | Sand-Shale | | |
| 1740 | 1750 | Shale | | |
| 1750 | 1941 | Red Bed | | |
| 1941 | 1976 | Anhydrite | | |
| 1976 | 2220 | Lime-Shale | | |
| 2220 | 2393 | Shale-Shells | | |
| 2393 | 2480 | Lime-Shale | | |
| 2480 | 2640 | Lime-Shale | 0° - 2500 | |
| 2640 | 2770 | Shale-Shell | 0° - 2750 | |
| 2770 | 2875 | Lime-Shale | | |
| 2875 | 2945 | Lime-Shale | | |
| 2945 | 3100 | Lime-Shale | 0° - 3000 | |
| 3100 | 3215 | Lime-Shale | | |
| 3215 | 3335 | Lime-Shale | 0° - 3250 | DST 3256-76' |
| 3335 | 3425 | Lime-Shale | | DST 3290-3315' |
| 3425 | 3550 | Lime-Shale | 0° - 3500 | DST 3439-53' |
| 3550 | 3605 | Lime-Shale | | |
| 3605 | 3617 | Granite Wash | | |

CASING LEFT IN HOLE AFTER COMPLETION

Set 346' of 8-5/8" OD Surface Casing (17 jts.)

RECEIVED
 STATE CORPORATION COMMISSION
 11-01-1956
 NOV 10 1956
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By Jay H. Galloway

Subscribed and sworn to before me this 7th day of November, 1956.

My commission expires:
 May 20, 1959

Vicky Jacobs
 Vicky Jacobs, Notary Public

PLUGGING
 FILE SEC. 1-1-27W
 BOOK PAGE 113 LINE 2