

STATE OF KANSAS
STATE CORPORATION COMMISSION


15-039-20484-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Decatur County, Sec. 2 Twp. 1S Rge. 27E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
S/2 SW NE

Lease Owner W. W. Sauvage
Lease Name Kilzer Well No. 2
Office Address 404 N. Penn, Oberlin, Kansas 67749
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Date Well completed 07-13 1980
Application for plugging filed 07-13 1980
Application for plugging approved 07-13 1980
Plugging commenced 07-13 1980
Plugging completed 07-13 1980

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3508'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

T.D. 3508'
Set 1st plug at 1200' with 60 sx.
2nd plug at 300' with 30 sx.
40' solid bridge with 10 sx.
Rathole with 5 sx. 50/50 posmix, 6% gel
Plug was down at 5:30 p.m. on 07-13-80.

RECEIVED
STATE CORPORATION COMMISSION
07-24-1980
JUL 24 1980
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Asst. Sec.-Treas (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of July, 1980

My commission expires _____



Sherrie L. Brooks
Sherrie L. Brooks Notary Public.

15-039-20484-00-00

CONTRACTOR'S WELL LOG

OPERATOR:	W. W. Sauvage
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	KILZER #2
LOCATION:	S/2 SW NE, Section 2-1S-27W Decatur County, Kansas
SPUD DATE:	07-08-80
COMPLETION DATE:	07-13-80

0	256	Clay, Sand & Blue Shale
256	316	Blue Shale
316	728	Shale
728	1976	Shale & Sand
1976	2000	Anhydrite
2000	2502	Shale & Sand
2502	2713	Shale
2713	2993	Shale & Lime
2993	3225	Lime & Shale
3225	3290	Lime, Shale & Sand
3290	3508	Lime
	3508	Rotary Total Depth

Spud hole at 1:30 p.m. 07-08-80. Drilled 316' in a 12-1/4" hole. Ran 8 joints new 8-5/8" casing (tally 317.69). Set at 315' with 240 sx. of 60/40 posmix, 3% c.c., 2% gel. Cement did circulate. Plug was down at 7:00 p.m. 07-08-80.

T.D. 3508'. Set 1st plug at 1200' with 60 sx., 2nd plug at 300' with 30 sx., 40' solid bridge with 10 sx., rathole with 5 sx. 50/50 posmix, 6% gel. Cement by Halliburton. Plug was down at 5:30 p.m. on 07-13-80.

SAMPLE TOPS:
Anhydrite 1976'
B/Anhydrite 2000'

RECEIVED
STATE CORPORATION COMMISSION
07-24-1980
JUL 24 1980
CONSERVATION DIVISION
Wichita, Kansas


STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the KILZER #2, S/2 SW NE, Section 2-1S-27W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
Jack L. Partridge, Asst. Sec.-Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state of this 22nd day of July, 1980

 SHERRIE L. BROOKS
Sedgwick County, Ks.
My Appt Exp. 8-27-82

Sherrie L. Brooks
Sherrie L. Brooks, Notary Public