


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

15-039-~~00176~~-00-00 ⁰⁰¹⁸¹ WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Decatur

County. Sec. 2 Twp. 1 Rge. 27 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW SW NW 1/4

Lease Owner Sauvage & Dunn Drilling Co., Inc.

Lease Name Kilzer Well No. 1

Office Address Oberlin, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed 1-29 19 57

Application for plugging filed 1-29 19 57

Application for plugging approved 1-29 19 57

Plugging commenced 1-30 19 57

Plugging completed 1-30 19 57

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3635 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|------|--------|------------|
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3615 to 280 feet to 280-40 feet for each plug set.

Filled hole with heavy mud on bottom pulled pipe to 1500 ft. and circulated with heavy mud. Pulled pipe and set plug 280 ft. Mixed 15 sx cement 1/2 sx hulls. thru drill pipe and filled with mud to 40 ft. set plug. 10 sx cement 1/2 sx hulls. filled surface casing to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____

Address _____

STATE OF Kansas, COUNTY OF Decatur, ss.

W. W. Sauvage (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. W. Sauvage
(Address) _____

SUBSCRIBED AND SWORN to before me this 1st day of February, 19 57

My commission expires May 17, 1959

W. W. Sauvage Notary Public.

PLUGGING
SEC 2 T 1 R 27 W
PAGE 137 OF 38



RECEIVED
STATE CORPORATION COMMISSION
02-04-1957
FEB - 4 1957

CONSERVATION DIVISION
Wichita, Kansas

Drillers Log

Operator: Sauvage & Dunn Drlg Co. Location: SW SW NW¹/₄ 2-1S-27W
 Farm Name: Kilzer Decatur County, Kansas
 Well No: #1 Casing Record: 286 ft. 8 5/8 "csg
 Contractor: Sauvage-Dunn Drlg. Co., Inc. 150 sx cement.
 Rotary Commenced: Jan. 20, 1957
 Rotary Completed: Jan. 30, 1957

00181
 15-039-~~00176~~-00-00

Figures denote bottom of formation

| | |
|-----------------------|------|
| Cellar | 5 |
| Shale | 381 |
| Shale | 875 |
| Shale & Shells | 1350 |
| Shale & Sand | 1630 |
| Shale & Shells | 1780 |
| Redbed | 1965 |
| Anyhdrite | 1975 |
| Anyhdrite | 1996 |
| Shale-Shells | 2080 |
| Shale and Red bed | 2380 |
| Shale and Shells | 2551 |
| Shale and Shells | 2670 |
| Shale and Shells | 2760 |
| Shale and Shells | 2860 |
| Shale and Shells | 2930 |
| Lime and Shale | 2987 |
| Shale and Lime | 3052 |
| Lime and Shale | 3145 |
| Lime and Shale | 3245 |
| Lime and Shale | 3300 |
| Lime and Shale | 3326 |
| Lime and Shale | 3371 |
| Lime | 3378 |
| Lime and Shale | 3440 |
| Lime and Shale | 3470 |
| Lime and Shale | 3525 |
| Lime and Shale | 3615 |
| Granite wash and Sand | 3635 |

State of Kansas
 County of Decatur

I hereby certify that the foregoing is, to the best of my knowledge and belief a full, true and correct drilling log as shown by the daily drilling reports in connection with the aforesaid well.

[Signature]
 For Sauvage & Dunn Drlg, Co., Inc.

Subscribed to and sworn to before me, the undersigned, a Notary Public, this 1st day of February, 1957.

[Signature]
 Notary Public

My Commission expires May 17, 1959

PLUGGING
 FILE SEC 2 T 1 R 27W
 BOOK PAGE 137 LINE 38

RECEIVED
 STATE COOPERATION COMMISSION
 02-04-1957
 FEB 4 1957
 CONSERVATION DIVISION
 Wichita, Kansas