


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Decatur County, Sec. 24 Twp. 1S Rge. (E)/27 (W)
Location as "NE/CNW/SW" or footage from lines C NE/4 NE/4
Lease Owner Abercrombie Drilling, Inc.
Lease Name POWELL Well No. 1
Office Address 801 Union Center; Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 1, 19 69
Application for plugging filed (verbally) October 1, 19 69
Application for plugging approved (verbally) October 1, 19 69
Plugging commenced October 1, 19 69
Plugging completed October 1, 19 69
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 3538 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	251'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.


Set 1st plug @1210' w/65 sx. cement;
Set 2nd plug @ 275' w/15 sx. cement;
Set top plug @ 40' w/10 sx. cement.
Job was completed at 8:15 a.m., 10-1-69.

RECEIVED
STATE CORPORATION COMMISSION
OCT 7 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Abercrombie Drilling, Inc. 10-7-1969
Address 801 Union Center; Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jerry A. Langrehr (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jerry A. Langrehr
801 Union Center; Wichita, Kansas (Address)



SUBSCRIBED AND SWORN to before me this 6th day of October, 1969
Sue J. Blunck, Notary Public.

15-039-20123-00-00

CONTRACTOR'S WELL LOG

OWNER: Abercrombie Drilling, Inc.
 CONTRACTOR: Abercrombie Drilling, Inc.
 LEASE: POWELL #1
 LOCATION: C NE/4 NE/4 Section 24-1S-27W
 Decatur County, Kansas
 SPUD DATE: September 25, 1969
 COMPLETION DATE: October 1, 1969
 GEOLOGIST: Jack K. Wharton

0	102	Sand and Clay
102	275	Shale
275	900	Shale and Shells
900	1120	Sand
1120	1575	Shale
1575	1668	Sand
1668	1890	Shale
1890	1918	Anhydrite
1918	2065	Shale and Lime
2065	3035	Lime and Shale
3035	3538	Lime
	3538	Total Depth

Drilled 255' of 12 $\frac{1}{4}$ " surface hole and set 8 5/8", 20# csg. @ 251' w/175 sx Sunset Cement. Cement circulated. Plug was down at 12:15 A.M. 9-25-69.
 Dry and Abandoned.

Electric Log Tops:		Elevation:
B/Ft. Hays	468 (+1956)	2424 K.B.
T/Anhydrite	1888 (+ 536)	2422 D.F.
B/Anhydrite	1916 (+ 508)	2416 G.L.
Heebner	3153 (- 729)	
Toronto	3190 (- 766)	
Lansing	3196 (- 772)	
B/K.C.	3405 (- 981)	
Granite Wash	3508 (-1084)	
Granite	3522 (-1098)	
E.L.T.D.	3535 (-1111)	

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 7 1969
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS.
 COUNTY OF SEDGWICK)

10-7-1969


Jerry A. Langrehr, Vice-President of Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the log of the POWELL #1, C NE/4 NE/4, Section 24-1S-27W, Decatur County, Kansas, as of this 3rd day of October, 1969.

ABERCROMBIE DRILLING, INC.

Jerry A. Langrehr
 Jerry A. Langrehr
 Vice-President

Sworn to before me, a Notary Public, in and for the County of Sedgwick, State of Kansas, as of the 3rd day of October, 1969.

Sue J. Blunck
 Sue J. Blunck
 Notary Public



My Commission Expires: July 15, 1972