


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Decator County. Sec 16 Twp. 1s Rge. 27W (E) (W)
Location as "NE/CNW/SW" or footage from lines SW SW SW
Lease Owner Sauvage Drilling Co.
Lease Name Kelzer Well No. 1
Office Address Oberlin, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed March 29 19 61
Application for plugging filed do 19
Application for plugging approved do 19
Plugging commenced do 19
Plugging completed do 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Al Fabricious, Hill City Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3640 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Shale				8 5/8	215	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 400 feet, set plug with 20 sax cement
filled hole to 150 feet-set plug with 20 sax cement- filled with mu
to 40 feet- set plug with 10 sax cement and filled to bottom of cellar

RECEIVED
STATE CORPORATION COMMISSION
4-5-61
APR 5 1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Company Tools 4-5-61
Address Oberlin, Kansas

STATE OF Kansas, COUNTY OF Decator, ss.
Keith Gallatin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Keith Gallatin
Keith Gallatin
Oberlin, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 1 day of April, 19 61

My commission expires June 18, 1962
Janice Bryan
Notary Public.



15-039-00431-00-00

OPERATOR Sauvage Drilling CO. Inc.
KARM NAME Helzer
WELL NO. 1
CONTRACTOR Company tools
ROTARY COMM 3-17-61
ROTARY COMP 3-29-61

LOCATION: 16-1s-27w
sw-sw-sw
Decator Co, Ka.
CASING RECORD: New 85/
surface casing

Figures denotes bottom of formation

Shale	
Shale and Shells	1581
Lime and Shale	
Anhydrite	1952
Shale and shells	1979
Lime	3069
Lime and shale	3439
Lime, Pyrite, chert	
Lime	
Regan	3566
Granite	3622-3640

RECEIVED
STATE CORPORATION COMMISSION
APR 5 1961
4-5-1961
CONSERVATION DIVISION
WELL, Kansas

STATE OF KANSAS)
) SS
COUNTY OF DECATOR)

Thereby certify that the foregoing is, to the best of my
Knowledge and belief, a true and correct drilling log as shown by
the drilling reports in connection with the aforesaid well.

Keith Gallatin
Keith Gallatin

Subscribed and sworn to before me, the undersigned
a Notary Public, this 29th day of March, 1961

James Bryan
Notary Public

My commission expires June 18, 1962