

State of Kansas



15-039-20063-00-00

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 28 1968

CONSERVATION DIVISION
Wichita, Kansas

10-28-1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Tom Buffington of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Buffington guarantees payment of the plugging fee.

Operator's full Name: Norman D. Fitzgerald,

Complete Address: Box #5046, Abilene, Texas.

Lease Name: Slim Macy Well No. 1

Location: NW-SW Sec. 11 Twp. 1 Rge. (E)(W) 29

County: Decatur Total Depth 2815 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole X

Mr. Buffington was instructed to plug the well as follows:

249'--8 5/8" Surface casing, cement circulated with 200 Sx.
Lost circulation @ 2115' and after repeated attempts to cement off loss
abandoned hole.

Run DP to 1475' and set 25 Sx. HA-5 "Hot" cement in an attempt to shut
off loss. Pull DP out of cement and let set for 2 hours. If plug holds
run DP back to 1400' and displace 100 Sx. cement thru DP. Pull DP to
275' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with
1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

M. S. Nichols
Conservation Division Agent