



ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 20 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
5-20-1968

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. W. E. Ogle of Petroleum Management, Inc., has this date requested permission to plug the following described well:

Mr. Ogle guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Incorporated,

Complete Address: 1515 Wichita Plaza Building, Wichita, Kansas.

Lease Name: McCartney Well No. 1

Location: SE-SE-NW Sec. 19 Twp. 1 Rge. (E)(W)29

County: Decatur Total Depth 4072 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ogle was instructed to plug the well as follows:

2 1/2'--8 5/8" Surface pipe, cement circulated with 200 Sx.

Circulate hole with heavy mud. Pull DP to 1550' and displace 100 Sx.

cement thru DP. Pull DP to 250' and displace 20 Sx. cement thru DP.

Pull DP, set bridge @ 40' and 10 Sx. cement to bottom of cellar.

Very truly yours,

N. L. Nichols  
Conservation Division Agent