



15-039-20196-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Clarence Michael of Sage Drilling Co., Inc., has this date requested permission to plug the following described well:

Mr. Michael guarantees payment of the plugging fee.

Operator's full Name: Rosen Oil Corporation,

Complete Address: 200 Sutton Place, Wichita, Kansas.

Lease Name: Templeton Well No. B-1

Location: CNE-SW Sec. 32 Twp. 1 Rge. (E)(W) 29

County: Decatur Total Depth 3940' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Michael was instructed to plug the well as follows:

230'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 1125'.

Circulate hole with heavy mud. Pull DP to 1350' and displace 100 Sx.  
cement thru DP. Pull DP to 245' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

RECEIVED

STATE CORPORATION COMMISSION

NOV 25 1970

CONSERVATION DIVISION  
Wichita, Kansas

11-25-1970

Very truly yours,

M. L. Nichols  
Conservation Division Agent