



15-039-20187-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 2 1970
CONSERVATION DIVISION
Wichita, Kansas
11-2-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Leo Swords of Murfin Drilling Company, has this date requested permission to plug the following described well:

Mr. Swords guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Company,

Complete Address: 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name: Macy Well No. B-1

Location: SE-SE-NW Sec. 11 Twp. 1 Rge. (E)(W) 29

County: Decatur Total Depth 4152' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Swords was instructed to plug the well as follows:

247'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota Section @ 1200'.

Circulate hole with heavy mud. Pull DP to 1425' and displace 100 Sx.
cement thru DP. Pull DP to 275' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent