



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
10-28-1963
OCT 28 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Mike Carr of Pubco Petroleum Corp. has this

date requested permission to plug the following described well:

Mr. Carr guarantees payment of the plugging fee.

Operator's full Name: Pubco Petroleum Corporation,

Complete Address: Box # 432, McCook, Nebraska.

Lease Name: Ackman-Green Well No. 8-I

Location: NE-SE Sec. 8 Twp. 1 Rge. (E) (W) 27

County Decatur Total Depth 3680 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Carr was instructed to plug the well as follows:

278'--8 5/8" Surface pipe, cement circulated.
3570'--2 7/8" Tubing, cemented with 160 Sx. Poz-Mix.
Bridging plug @ 3370', Top of perforations @ 3299'.

Sand well back to 3285' and set 1 sack cement. Pull 2 7/8"

tubing to 600' circulate heavy gel mud and displace 20 Sx

cement thru tubing. ~~RM~~ Pull tubing to 270' and displace 20
Sx cement. Pull tubing, set bridge @ 35' and 10 Sx cement to
bottom of cellar.

Very truly yours,

M. L. Tschel
Conservation Division Agent