

RECEIVED
APR 07 2004
KCC WICHITA

W E N E S E

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Sophia Dreiling

WELL NUMBER 1

2310 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 28 TWP. 13S RGE. 17 ~~XX~~ or (W)

COUNTY Ellis

Date Well Completed 3-31-52

Plugging Commenced 4-5-04

Plugging Completed 4-5-04

LEASE OPERATOR Dreiling Oil, Inc.

ADDRESS Box 550 Hays, KS 67601

PHONE# (785) 625-8327 OPERATORS LICENSE NO. 5145

Character of Well Oil

(Oil, Gas, D3A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-3-04 (date)

by Herb Deines (KCC District Agent's Name).

Is KCC-1 filled? Yes If not, is well log attached? 3420

Producing Formation Lansing/KC Depth to Top 3212' Bottom 3420'
Arbuckle Depth to Top 3485' Bottom 3507' T.D. 3507'

Give depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Lansing/KC	oil & water	3212'	3420'	8 5/8"	90'	None
Arbuckle	oil & water	3485'	3507'	5 1/2"	3485'	None
<i>Surg Prod</i>			90'	8.625"	90'	<i>D</i>
			3485'	5.50"	3485'	<i>D</i>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each set.
Ran tubing to 870'. Moxed 70 sx. 60/40 poz, 10% gel & cement circ. Pulled tubing. Tied to 8 5/8" & mixed 25 sx. 60/40 poz., 10% gel. Pump pressure 350#. SIP - 100%. Hooked to 5 1/2" casing & mixed 100 sx. 60/40 poz., 10% gel. at 500# to 350#. SIP - 100%. Job complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. / Express Well Service & Supply, Inc. License No. 99996 6426

Address Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Dreiling Oil, Inc.

STATE OF KANSAS COUNTY OF ELLIS, ss.

I, Terry Piesker (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Terry W. Piesker

(Address) Box 550 Hays, KS 67601

Notary Public State of Kansas

Patricia Dreiling

My Appt Exp

SUBSCRIBED AND SWORN TO before me this 5th day of April ~~xxx~~ 2004

Patricia Dreiling
Notary Public

My Commission Expires: 8-23-06