

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-051-04940-00-00  
LEASE NAME Carmichael

WELL NUMBER #1  
NOTICE: Fill out completely and return to Cons. Div. office within 30 days  
2970 Ft. from S Section Line  
4620 Ft. from E Section Line

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 11 TWP 11SRGE. 18W (E) or (W)  
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY Ellis  
PHONE # (316 ) 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 5/24/41  
Character of Well Oil (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 3/30/04  
Plugging Completed 3/30/04

The plugging proposal was approved on 3/30/04 2-19-04 (date)  
by Roger Moses w/ KCC in Hays, KS (KCC District Agent's Name)

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? Not provided by former operator \_\_\_\_\_

Producing Formation Arbuckle Depth to Top 3378 Bottom 3424 TD3425 Show depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		Surface	1180	8 5/8	1180	0
		Production	3424	5 1/2	3424	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Plugged well as follows:

MIRU MDC #716. 5 1/2" csg to 3424, CIBP @3410, TIH w/100 jts 2 3/8" tbg = 3400', RU Allied Cementing tie onto tbg. Mix & pump 100 sks 60/40 10% gel w/ 300# hulls, TOH w/ 55 jts tbg to 1700' mix & pump. 165 sks & 200# hulls circ cmt to surface up 8 5/8" & 5 1/2", TOH w/ tbg off w/ 25 sks. Plugged @ 1:15pm used 290 sks & 500# hulls witnessed by Roger Moses w/KCC.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606  
Address 250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]  
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 9th day of April, 2004

Notary Public - Kristin Grady Kristin Grady  
My Commission Expires: 2/06/08 Form CP-4 Revised 05-88



RECEIVED [Signature]  
APR 12 2004  
KCC WICHITA

# ALLIED CEMENTING CO., INC. 13694

Federal Tax I.D.# ~~45-27770~~

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:

Oakley

DATE <u>3-30-04</u>	SEC <u>11</u>	TWP. <u>113</u>	RANGE <u>18w</u>	CALLED OUT	ON LOCATION <u>10:00 AM</u>	JOB START <u>11:00 AM</u>	JOB FINISH <u>1:15 PM</u>
LEASE <u>Carmichael</u>	WELL # <u>1</u>	LOCATION <u>Hays 14N 1 1/2 E</u>			COUNTY <u>Ellis</u>	STATE <u>KS</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR Murfin Drly Co

TYPE OF JOB Plug old hole

HOLE SIZE \_\_\_\_\_ T.D. \_\_\_\_\_

CASING SIZE 5 1/2 DEPTH \_\_\_\_\_

TUBING SIZE 2 3/8 DEPTH 3400'

DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_

MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_

CEMENT LEFT IN CSG. \_\_\_\_\_

PERFS. \_\_\_\_\_

DISPLACEMENT \_\_\_\_\_

OWNER Same

CEMENT AMOUNT ORDERED

375 sks 60/40 Poz 10% Gel

Used 290 sks 500 # Halls

COMMON	<u>174 sks</u>	@ <u>8.35</u>	<u>1452.90</u>
POZMIX	<u>116 sks</u>	@ <u>3.80</u>	<u>440.80</u>
GEL	<u>25 sks</u>	@ <u>10.00</u>	<u>250.00</u>
CHLORIDE	_____	@ _____	_____
	_____	@ _____	_____
	_____	@ _____	_____
	_____	@ _____	_____
	_____	@ _____	_____
HANDLING	<u>320 sks</u>	@ <u>1.15</u>	<u>368.00</u>
MILEAGE	_____	_____	<u>656.00</u>

**EQUIPMENT**

PUMP TRUCK CEMENTER Dean

# 373-271 HELPER Fuzzy

BULK TRUCK

# 361 DRIVER Jarrod

BULK TRUCK

# 212 DRIVER Lonnie

RECEIVED TOTAL 3257.70

APR 12 2004

**REMARKS:**

Tub at 3400', mix 100 sks w/300#  
Halls & Disp. Pulled Tub to 1700'  
circulated cement to surface  
B side & csg w/165 sk & 200#  
Halls. Pulled Tub. Tap off  
w/25 sks

KCC WICHITA SERVICE

DEPTH OF JOB \_\_\_\_\_

PUMP TRUCK CHARGE \_\_\_\_\_ 250.00

EXTRA FOOTAGE \_\_\_\_\_ @ \_\_\_\_\_

MILEAGE 41 miles @ 3.50 143.50

PLUG \_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

TOTAL 393.50

*Thank You*

CHARGE TO: Murfin Drly Co Inc

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

**FLOAT EQUIPMENT**

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Mark Roller

TOTAL \_\_\_\_\_

TAX \_\_\_\_\_

TOTAL CHARGE \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

PRINTED NAME