

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-055-20167-00-00

LEASE NAME Faldtz

WELL NUMBER 1-35 35-1

1320 Ft. from N Section Line

1320 Ft. from W Section Line

SEC. 35 TWP. 23 RGE. 33W (E) or (W)

COUNTY Finney

Date Well Completed 02/06/76

Plugging Commenced 03/31/04

Plugging Completed 03/31/04

RECEIVED

APR 15 2004

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

KCC WICHITA

LEASE OPERATOR Chesapeake Operating, Inc.

ADDRESS P. O. Box 18496, Oklahoma City, OK 73154-0496

PHONE# (409) 848-8000 OPERATORS LICENSE NO. 32334

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 05/29/04 (date)

by David Williams (KCC District Agent's Name).

Is ACO-1 filed? Yes if not, is well log attached? _____

Producing Formation Krider Depth to Top 2569' Bottom 2579' T.D. 2650'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Surf</u>			<u>388</u>	<u>8-5/8</u>	<u>388'</u>	388'
<u>Perf</u>			<u>2649</u>	<u>5-1/2</u>	<u>2649'</u>	2649'
<u>SIW</u>			<u>2500</u>			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. MIRU Superior WS, lay out rods & tbg. RDMO, RU Log-Tech of KS, set CIBP @2500' w/25 sx cmt, MIRU Allied, load hole w/mud, pressure test csg to 500#, OK, perf @1050', press up to 1500#, unable to, reperf @800', pump into @1300#, pump 150 sx cmt down 5-1/2", max PSI 1300#, SI @200#, attempt to pump down 8-5/8", leak @GL, displace cmt down 5-1/2" to 390', did not circ., reperfed @ 360', circ to surf, pump 125 sx cmt, SIW, RDMO, pump 60/40 poz 6% gel

Name of Plugging Contractor Allied Cementing Co., Inc. License No. 99996

Address P. O. Box 31, Russell, KS 67665 (785)483-2626

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Chesapeake Operating, Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Jim Reisch (Employee of Operator) or (Operator) o

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Barbara J. Bale for Jim Reisch
Jim Reisch

(Address) P.O. Box 18496, Okla. City, OK

SUBSCRIBED AND SWORN TO before me this 13th day of April, 2004

My Commission April 17, 2007
Jamie R. Brody
Notary Public



Bm

ALLIED CEMENTING CO., INC. 14022

Federal Tax I.D.# ~~XXXXXXXXXX~~

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
OAKLEY

DATE: <u>3-31-04</u>	SEC: <u>35</u>	TWP: <u>26S</u>	RANGE: <u>33W</u>	CALLED OUT	ON LOCATION: <u>8:45 AM</u>	JOB START: <u>9:00 AM</u>	JOB FINISH: <u>12:45 PM</u>
LEASE: <u>FALOTZ</u>	WELL #: <u>1-35</u>	LOCATION: <u>GARDEN CITY 4N-2W-35-1/4E</u>		COUNTY: <u>FINNEY</u>		STATE: <u>KS</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)				S INTO			

CONTRACTOR NONE OWNER NONE

TYPE OF JOB OLD Hole

HOLE SIZE _____ T.D. _____

CASING SIZE 5 1/2" DEPTH _____

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

CEMENT

AMOUNT ORDERED 350 SKS 60/40 P02 6266 L

400 # Hull

450 275 SKS 60/40 P02 6266 L

COMMON	<u>165 SKS</u>	@	<u>8.35</u>	<u>1377.75</u>
POZMIX	<u>110 SKS</u>	@	<u>3.82</u>	<u>418.20</u>
GEL	<u>14 SKS</u>	@	<u>10.00</u>	<u>140.00</u>
CHLORIDE		@		
		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>372 SKS</u>	@	<u>1.15</u>	<u>427.80</u>
MILEAGE	<u>0.54 PER SK/MI</u>			<u>130.20</u>
TOTAL				<u>3665.95</u>

EQUIPMENT

PUMP TRUCK CEMENTER: TERRY

177 HELPER: WAYNE MAX

BULK TRUCK DRIVER: RONNIE

361

BULK TRUCK DRIVER _____

REMARKS:

SET BRIDGE PLUG AT 2500'. TEST PLUG TO 500 PSI. HELD PERF AT 1050' COULD NOT PUMP INTO IT. PERF AT 800' MIX 150 SKS DOWN 5 1/2" CASING DISPLACE TO 425'. PERF AT 360' MIX 125 SKS CEMENT & CIRC TO SURFACE OUT BACKSIDE.

THANK YOU

SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE _____ 475.00

EXTRA FOOTAGE _____ @ _____

MILEAGE 70 @ 3.50 245.00

PLUG _____ @ _____

_____ @ _____

_____ @ _____

TOTAL 720.00

CHARGE TO: CHESAPEAKE OPERATING

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Dennis Dief

Dennis Frick
PRINTED NAME

RECEIVED
APR 15 2004
KCC WICHITA

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS