

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-175-20307-00-00

LEASE NAME Betty Lemert

WELL NUMBER #1

660 Ft. from N Section Line

1980 Ft. from E Section Line

SEC. 22 TWP. 32 RGE. 33W (E) or (W)

COUNTY Seward

Date Well Completed 07/27/77

Plugging Commenced 03/24/04

Plugging Completed 03/24/04

RECEIVED

APR 15 2004

KCC WICHITA

LEASE OPERATOR Chesapeake Operating, Inc.

ADDRESS P. O. Box 18496, Oklahoma City, OK 73154-0496

PHONE# (405) 848-8000 OPERATORS LICENSE NO. 32334

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 08/21/03 (date)

by David Williams (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation MRMN Chester Depth to Top 4784' Bottom 4920'
5654' 5774' T.D. 6011'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Sand</u>			<u>1600</u>	<u>8-5/8</u>	<u>1600</u>	<u>S</u>
<u>Clay</u>			<u>6010</u>	<u>5-1/2</u>	<u>6010</u>	<u>S</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. MIRU Allied, pump down 5-1/2" csg w/300# hulls & 25 sx cmt, follow bottom plug w/120 bbls mud spacer, press to 500#, OK, RU Rosel, RTH, perf @1600', RDMO, RU Allied, pump 400 sx cmt down 5-1/2"x8-5/8" annulus from 1600' to surface, ST @ 100#, RDMO, P&A final

Name of Plugging Contractor Allied Cementing Co., Inc. License No. 99994

Address P. O. Box 31, Russell, KS 67665 (785)483-2626

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Chesapeake Operating, Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Jim Reisch

(Employee of Operator) or (Operator) o

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Barbara J. Bale for Jim Reisch

Jim Reisch

(Address) P.O. Box 18496, Okla. City, OK

73154-0496

SUBSCRIBED AND SWORN TO before me this 13th day of April, 2004

Jamie R. Brody

Notary Public

My Commis. Expires: April 17, 2007



Bm

ALLIED CEMENTING CO., INC. 14300

Federal Tax I.D.# ~~XXXXXXXXXX~~

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Oakley

DATE <u>3-24-04</u>	SEC. <u>22</u>	TWP. <u>32s</u>	RANGE <u>33w</u>	CALLED OUT	ON LOCATION <u>9:10AM</u>	JOB START <u>9:30AM</u>	JOB FINISH <u>1:30PM</u>
LEASE <u>Lemert Berry</u>	WELL.# <u>1-22</u>	LOCATION <u>Sublette 14 S 1W 12.5</u>			COUNTY <u>Seward</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one)					<u>W/S</u>		

CONTRACTOR _____ OWNER Sqme

TYPE OF JOB Plug old hole

HOLE SIZE _____ T.D. _____

CASING SIZE 5 1/2 DEPTH _____

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. 4784-4920' + 5654-5774'

DISPLACEMENT _____

CEMENT AMOUNT ORDERED 425 sks 60/40 626 gal 3000 Hulls

COMMON	<u>255 sks</u>	@	<u>8.35</u>	<u>2129.25</u>
POZMIX	<u>170 sks</u>	@	<u>3.80</u>	<u>646.00</u>
GEL.	<u>22 sks</u>	@	<u>10.00</u>	<u>220.00</u>
CHLORIDE		@		
	<u>Hulls 3 sks</u>	@	<u>18.00</u>	<u>54.00</u>
		@		
		@		
		@		
HANDLING	<u>450 sks</u>	@	<u>1.15</u>	<u>517.50</u>
MILEAGE	<u>59 sk/mile</u>			<u>405.00</u>

EQUIPMENT

PUMP TRUCK CEMENTER Dean

373-281 HELPER Andrew

BULK TRUCK

361 DRIVER Mike

BULK TRUCK

_____ DRIVER _____

TOTAL 3971.75

REMARKS:

pump 250# Hulls followed w/ 255sk cement w/ 50# Hulls & Disp w/ Mud. Perf at 1600' circulated cement to surface w/ 400SKS.

Thank You

SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE _____ 580.00

EXTRA FOOTAGE @ _____

MILEAGE 18 Miles @ 3.50 63.00

PLUG @ _____

@ _____

@ _____

TOTAL 1643.00

CHARGE TO: Chesapeake Operating

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

@ _____

@ _____

@ _____

@ _____

@ _____

TOTAL _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Dennis Dick

Dennis Dick
PRINTED NAME

RECEIVED
APR 15 2004
KCC WICHITA