

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-195-21571-00-00

LEASE NAME Morton

WELL NUMBER 2

330 Ftt. from S Section Line

990 Ftt. from E Section Line

SEC. 7 TWP. 13 RGE. 21 (E) or (W)

COUNTY Trego

Date Well (Completed) \_\_\_\_\_

Plugging Commenced 3/17/04

Plugging Completed 3/17/04

RECEIVED

APR 14 2004

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR KCC WICHITA Encore Operating Company

ADDRESS 1601 Blake St, Suite 500, Denver, CO

PHONE (303) 595-9251 OPERATORS LICENSE NO. 33069

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 17, 2004 10-13-04 (date)

by Jay Pfiefer (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Marmaton Depth to Top 3892 Bottom 3922 T.D. 4047

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface Casing	.0	218	8 5/8	<u>218</u>	none
	Producing Casing	0	4098	5 1/2	<u>4098</u>	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Hooked up to 8 5/8" casing and pumped 10 sacks of 60%40 P05 w/10% Gel Cement and pressured to 500#'s Ran 2" tubing to 2100 ft. circulated 190 sacks of cement and 500#'s of hull to surface. Pulled tubing, pumped 100 sacks of cement down the 5 1/2" casing at 500#'s pressure ISIP 150#'s cement in the 5 1/2" casing from surface to 3892', plug down at 12:30 pm.

Name of Plugging Contractor Fischer Well Service Company License No. 99998 02332

Address Ellis, KS.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Encore Operating Company

STATE OF Colorado COUNTY OF Denver, s.s.

Roland Nyp

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Roland Nyp

(Address) 804 MAIN STOCKTON KS

SUBSCRIBED AND SWORN TO before me this 9 day of April, 2004

Steve R Nyp  
Notary Public

