

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-039-20567-00-00

LEASE NAME Huff

WELL NUMBER 1

SWSE Ft. from S Section Line

Ft. from E Section Line

SEC. 10 TWP. 1S RGE. 27W (E) or (W)

COUNTY Decatur

Date Well Completed 2-10-81

Plugging Commenced 4-20-87

Plugging Completed 4-20-87

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR NICOR Exploration

ADDRESS 1667 Cole Blvd., Golden, CO 80401

PHONE#(303) 232-9292 OPERATORS LICENSE NO. 5342

Character of Well Oil 9995

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? District #6, Hays Office (Carl Goodrow witnessed job)

Is ACO-1 filed? Yes If not, is well log attached? No

Producing Formation Lansing-Kansas Depth to Top 3216 Bottom 3422 T.D. 3608

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing Kansas City	Oil & Water	0	330	8-5/8"	2/81	---
		0	3543	4 1/2"	2/81	---

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Bullheaded 100 sx Econolite (62 BBLs slurry) down tubing. Pumped 6 BBLs slurry, added 300 lbs cotton seed hulls in next 10 BBLs & pumped remaining 46 BBLs. Had 300 psi pump pressure. Bullheaded 100 sx Econolite (57 BBLs slurry) down annulus. Pumped 6 BBLs slurry, added 200 lbs cotton seed hulls in next 10 BBLs (If additional description is necessary, use BACK of this form.) (cont'd)

Name of Plugging Contractor Halliburton Services License No. 5287

Address P. O. Box 24, Oberlin, Kansas 67749 (Attn: Terry Garrison 913-475-2228)

STATE OF Colorado COUNTY OF Jefferson, ss.

Richard T. Griebeling (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

STATE CORPORATION COMMISSION

08-04-1987

AUG 4 1987

(Signature) Richard T. Griebeling (Address) 1667 Cole Blvd., Golden, CO 80401

SUBSCRIBED AND SWORN TO before me this 28th day of July, 1987

CONSULTING DIVISION  
Wichita, Kansas

P. J. Sherman  
Notary Public

My Commission Expires: January 13, 1991

and pumped remaining 41 BBLS. Had 1000 psi + shut down 1/2 BBL short.