


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

15-039-00474-00-00

Decatur County. Sec. 11 Twp. 1 Rge. (E) 27 (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SE NW  
Lease Owner Cities Service Oil Co.  
Lease Name Redman Well No. 1  
Office Address Bartlesville, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed 6/8/56 19...  
Application for plugging filed 6/8/56 19...  
Application for plugging approved 6/12/56 19...  
Plugging commenced 6/8/56 19...  
Plugging completed 6/8/56 19...  
Reason for abandonment of well or producing formation.....



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production..... 19...  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty  
Producing formation..... Depth to top..... Bottom..... Total Depth of Well 3514 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	320'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Filled hole with mud to 300' of surface, set wood plug, dumped  $\frac{1}{2}$  sack hulls mixed 15 sx. of cement.  
Filled hole with mud to 40' of surface set wood plug, dumped  $\frac{1}{2}$  sack of hulls mixed 10 sacks of cement to surface.

06-21-56  
JUN 21 1956  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lohmann-Johnson  
Address Evansville, Indiana

STATE OF KANSAS, COUNTY OF BARTON, ss.  
M. M. Hardin (employee of owner) or owner of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M M Hardin

Box 553, Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 70th day of June, 19 56

My commission expires March 12, 1959

PLUGGING  
FILE SEC 11 T 1 R 27W  
BOOK PAGE 70 LINE 4

Notary Public.

# WELL RECORD

15-039-00474-00-00

Company Ottawa Service Oil Company Well No. 1 Farm Rehman

Location 320' North and 970' West of Center Sec. 11 T. 1 R. 27

Elevation 2497 (2496 Cr.) County Dwight State Kansas

Drlg. Comm. May 26, 1956 Contractor Lehman-Johnson Drilling Co., Inc.

Drlg. Comp. June 8, 1956 Acid None

T. D. 3514' Initial Prod. Dry Hole - P. & A. 6-6-56

### LOGGING RECORD:

5-1/8" @ 325' ann. 250 on cement

### FORMATION RECORD:

sand & shale	0-350
shale	355
sand & shale	1530
shale & shells	1700
shale	1810
anhydrite	1880
shale	1900
lime	2195
shale & lime	2500
lime & shale	2650
lime	2817
shale & lime	3014
lime	3160
cored shale & lime (rec. 12')	3172'
cored lime & shale (rec. 23 1/2')	3197 1/2'
cored lime & shale (rec. 19 1/2')	3217
cored lime & shale (rec. 8')	3225
cored shale & lime (rec. 25')	3250
cored lime & shale (rec. 26')	3277
cored lime & shale (rec. 37 1/2')	3314 1/2'
cored lime & shale (rec. 34 1/2')	3351
cored lime & shale (rec. 12')	3363
cored lime & shale (rec. 22 1/2')	3386 1/2'
lime	3459
lime & shale	3500
Granite Wash	3514 T. D.

Anhydrite	1870'
Howard	2090'
Topok	3006'
Hochner	3132'
Rodge	3145'
Lanning	3166'
Base Kansas City	3378'
Seagan	3400'
Granite Wash	3500'
Penetration	14'
Total Depth	3514'

D. S. T. 2910-42, open 1 hr., recovered 22' mud with spots oil; B. H. P. 2550/30 mins.

D. S. T. 3095-3130, open 1 hr., recovered 51' mud with spots oil; B. H. P. 2650/30 mins.

D. S. T. 3421-3500, open 45 mins., recovered 2295' salt water; no B. H. P. obtained.

SLOPE TESTS: (STVO)	500'	0°
	1000'	0°
	1500'	0°
	2000'	0°
	2500'	0°

PLUGGING

PLUGGING
FILE SEC <u>11</u> T <u>1</u> R <u>27W</u>
BOOK PAGE <u>70</u> LINE <u>4</u>