

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

15-039-00198-00-00

Decatur County, Sec. 23 Twp. 1S Rge. 30 (W)

Location as "NE/CNW/SW" or footage from lines C SW SW

Lease Owner Rains & Williamson Oil Co.

Lease Name Waldo Well No. 1

Office Address 412 Union Center, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 1-3 19 63

Application for plugging filed 1-3 19 63

Application for plugging approved 1-3 19 63


Plugging commenced 1-3 19 63

Plugging completed 1-4 19 63

Reason for abandonment of well or producing formation No oil or gas found in commercial quantities.

If a producing well is abandoned, date of last production ----- 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Bill Nichols, Moreland, Kansas

Producing formation None Depth to top ----- Bottom ----- Total Depth of Well 4356 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	247'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ----- feet to ----- feet for each plug set.

Set first plug at 540', cement through drill pipe with 20 sacks cement. Filled up with rotary mud to 180'. Cement through drill pipe with 20 sax. Filled up to 35' of base of cellar. Cap with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
01-08-1963
JAN 8 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co.

Address 412 Union Center, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wilson Rains - Partner

XXXXXXX (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
Wilson Rains
412 Union Center - Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of January, 19 63

My commission expires November 8, 1966

Sherry Gish
Sherry Gish Notary Public.



ROTARY DRILLING LOG

15-039-00198-00-00

OPERATOR: Rains & Williamson Oil Co.
 NO. 1 WALDO
 C SW SW Sec. 23-18-30W
 Decatur County, Kansas

CONTRACTOR: Rains & Williamson Oil Co.
 COMMENCED: 12-26-62
 COMPLETED: 1-3-63

Remarks: Set 8-5/8" surface casing
 at 247' with 150 sack
 quick cement.

Formations:

Sand and Shale	250'
Shale	1080'
Sand and Shale	1720'
Shale and Shells	2185'
Lime	2190'
Shale and Lime	2425'
Shale	2427'
Anhydrite	2458'
Shale and Lime	2820'
Lime and Shale	3200'
Shale and Lime	3365'
Lime and Shale	3510'
Lime	3855'
Shale and Lime	3910'
Sh. and Shale	4120'
Lime	4190'
Lime (Arkuckle)	4295'
Lime	4356'
Rotary Total Depth (D & A)	4356'

RECEIVED
 STATE CORPORATION COMMISSION
 01-08-1963
 JAN 8 1963

CONSERVATION DIVISION
 Wichita, Kansas

We certify the above log is true
 and correct to the best of our know-
 ledge and belief.

RAINS & WILLIAMSON OIL CO.

Wilson Rains
 Wilson Rains
 Partner

Subscribed and sworn to before me, a Notary
 Public in and for the State of Kansas, County of
 Sedgwick, this 7th day of January, 1963.

Sherry Gish
 Sherry Gish Notary Public

My Commission Expires:

NOVEMBER 3, 1966