

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-20199-00-01  
Spot: SWNWNE Sec/Twnshp/Rge: 24-14S-15W  
4290 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: EICHMAN Well #: 1-A  
County: RUSSELL Total Vertical Depth: 3255 feet

Operator License No.: 3134  
Op Name: MORRIS, TERRY E. DBA G L M COMPA  
Address: PO BOX 193  
RUSSELL, KS 67665

PROD Size: 5.5 feet: 3255 125 SX CMT  
SURF Size: 8.625 feet: 900 450 SX CMT

# 105<sup>19</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/09/2004 11:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/09/2004 1:45 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Sanded to 2980' and dumped 5 sxs cement.  
Cut at 1400' and 900'. Did not come loose.  
Pumped 75 sxs 60/40 pozmix - 10% gel cement.  
Cut at 600' - not loose.  
Pumped 60 sxs cement down 5 1/2" casing.  
Max. P.S.I. 300#. S.I.P. 200#.  
Pumped 25 sxs cement down backside.  
Max. P.S.I. 300#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3173	3176		
3028	3046		

RECEIVED  
APR 06 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

MD

Signed \_\_\_\_\_

*Case Morris*

(TECHNICIAN)

INVOICED

DATE

4-6-04

INV. NO.

2004061393

APR 02 2004

STANDARD OIL OPERATION  
 BOX 572, RUSSELL, KS.

#1 EICHMAN "OWO"

24-14-15W  
 SW NW NE

CONTRACT EPHIASIS OIL OPERATIONS CTY RUSSELL

FIELD GORHAM

1835 KB CM 4/5/76 CARD ISSUED 12/21/78 IP P 20 BOPD & WTR  
 ARB - INTV UNKNOWN

+	+
+	+
+	+

API 15-167-20,199-A

SMP	TOPS	DEPTH	DATUM
HEEB		2949	-1114
TOR		2968	-1133
LANS		3007	-1172
ARB		3242	-1407
TD		3255	-1420

OLD INFO: OPERATOR WAS MORRIS SITRIN, INC. #1-A EICHMAN; SPD 6/19/68, SET 8" 900/450SX; COMPLETED AS D&A/ARB/7/3/68 DST (1) 3243-48/20", REC 5'M, SIP 0-15", FP 0-0".

NEW INFO: RE-ENTERED 4/5/76, CO 3255, 4 1/2" SET - TSTD, ARB (INTERVAL UNKNOWN) POP, P 20 BOPD & WTR, NO OTHER INFO RELEASED BY OPERATOR

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

439124