


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Decatur County, Sec. 28 Twp. 1S Rge. 29W E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
70' E of SW NW SW

Lease Owner F & M Oil Company
Lease Name MOORE Well No. 1
Office Address 422 Union Center, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed Jan. 13 19 80
Application for plugging filed (verbally) Jan. 13 19 80
Application for plugging approved (verbally) Jan. 13 19 80
Plugging commenced Jan. 13 19 80
Plugging completed Jan. 13 19 80

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4090'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

T.D. 4090'
Set 1st plug at 1320' with 70 sacks
2nd plug at 240' with 20 sacks
3rd plug at 40' solid bridge with 10 sacks
rathole with 5 sacks.
Cemented with 50/50 posmix, 6% gel.
Plug was down at 7:15 a.m., 01-13-80.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of January, 1980



Sherrie L. Brooks
Sherrie L. Brooks Notary Public.

My commission expires 08-21-82

RECEIVED
STATE CORPORATION COMMISSION
1-17-1980
JAN 17 1980

CONSERVATION DIVISION
Wichita, Kansas

15-039-20479-00-00

CONTRACTOR'S WELL LOG

OPERATOR:	F & M Oil Company
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	Moore #1
LOCATION:	70' E of SW NW SW, Section 28-1S-29W, Decatur County, Kansas
SPUD DATE:	January 05, 1980
COMPLETION DATE:	January 13, 1980

0	245	Surface clay, sand and shale
245	620	Shale
620	1620	Shale and sand
1620	1960	Shale
1960	2300	Shale and sand
2300	2332	Anhydrite
2332	2821	Shale
2821	3387	Lime and shale
3587	4090	Lime
	4090	Rotary Total Depth

Spud hole at 5:15 p.m., January 05, 1980. Drilled 245' of 12 1/4" hole. Ran 6 joints of 8-5/8" used 24# casing. (Talley 235.94') Set at 244'. Cemented with 190 sacks of common cement, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 1:45 a.m., January 06, 1980.

T.D. 4090'. Set 1st plug at 1320' with 70 sacks, 2nd plug at 240' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks, rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 7:15 a.m., January 13, 1980.

SAMPLE TOPS:

Anhydrite 2300'
B/Anhydrite 2332'


STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Moore #1, 70' E of SW NW SW, Section 28-1S-29W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
Jack L. Partridge
Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 16th day of January, 1980.



Sherrie L. Brooks
Sherrie Brooks, Notary Public

My commission expires 08-21-82.

RECEIVED
STATE CORPORATION COMMISSION
1-17-1980
JAN 17 1980

CONSERVATION DIVISION
Wichita, Kansas