

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-051-25250-0000

API NUMBER 15-033-25250

LEASE NAME Schlegel

WELL NUMBER 1-33

4950 Ft. from S Section Line

4490 Ft. from E Section Line

SEC. 33 TWP. 15 RGE. 17 (E) or (W)

COUNTY Ellis

Date Well Completed \_\_\_\_\_

Plugging Commenced 03/10/2004

Plugging Completed 03/11/2004

RECEIVED

MAR 16 2004

KCC WICHITA

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Lario Oil & Gas Company

ADDRESS 301 S. Market Street; Wichita, KS 67202

PHONE#( ) 316-265-5611 OPERATORS LICENSE NO. 5214

Character of Well Dry Hole

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 02/12/2004 (date)

by Completing Form CP-1 Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? Yes - Attached If not, is well log attached? \_\_\_\_\_

Producing Formation Arbuckle attempted @ Depth to Top 3488 Bottom 3504 T.D. 3606

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Conductor		0	90	13-3/8"	90	None
Surface		0	1040	8-5/8"	1040	None
Production		0	3606	5-1/2"	3604	2700'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set

Spotted sand to 50' above Arbuckle perms. Dumped 5 sks cmt on top. Pull csa & spot 3 plugs as follows:

(1) 110 sks+300# cottonseed hulls @ 1700'; (2) 40 sks+200# cottonseed hulls @ 1030';

(3) 60 sks from surface to 300'. Cement plugs are 60/40 Pozmix + 10% gel. Witness by KCC Rep. Case Morris

Name of Plugging Contractor Quality Well Service Inc. License No. 31925

Address 415 E Main St. Sterling, KS 67579 620-727-3410

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lario Oil & Gas Company

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jay G. Schweikert, Operations Engineer (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Jay G. Schweikert

(Address) 301 S. Market Street; Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 15 th day of March, 2004

Kathy L. Ford  
Notary Public

KATHY L. FORD  
Notary Public - State of Kansas  
My Appt. Expires 10-22-06

My Commission Expires: 10-22-06