

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. MARKET, ROOM 207
WICHITA, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

~~15-155-39265-0000~~
15- 06/26/58

15-155-19031-00-01

API NUMBER _____
LEASE NAME Adkins

RECEIVED

TYPE OR PRINT

NOTICE: Fill out Completely
and return to cons. div.
office within 30 days.

WELL NUMBER 1
990

MAR 18 2004

_____ ft. from S Section Line
2310 ft. from E Section Line

KCC WICHITA
R & B Oil & Gas, Inc.

SEC. 15 TWP. 26 RGE. 9 (E) or (W)

LEASE OPERATOR _____

COUNTY Reno

ADDREES Box 195, Attica, KS 67009

Date Well Completed ~~NA~~ 8-1-1958

PHONE # (620) 254-7251 OPERATORS LICENSE NO. 31191

Plugging Commenced 2/3/04

Character of well oil

Plugging Completed 2/9/04

(Oil, Gas, D&A, SWD, input, Water Supply Well)

The plugging proposal was approved on 2/3/04 (date)

by Doug LOUIS (XCC District Agent's Name)

Is ACO-1 filed? yes if not, Is well log attached? not available to us

Producing Formation Mississippi Depth to Top NA Bottom NA T.D. 4153

Show depth and thickness of all water, oil and gas formations

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8		
Mississippi	oil ^{per Oper 3/22/04} Gas	NA	NA	5 1/2	4152	2620
Prod			452	5.5	4152	2620

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set

Sand at 3350, bail 5 sacks cement. Ripped pipe at 2620, pulled 40 joints to 1300, well blew out. Swedged in. Allied pumped 35 sacks 2% cc at 1300. Pulled to 800 and pumped 35 sacks 2% cc. pulled to 285, circulated with 160 sacks cement.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925

Address 401 West Main, Lyons, KS 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R & B Oil & Gas, Inc.

STATE OF KANSAS COUNTY OF Harper, ss.

Randy Newberry (Employee of Operator) or (Operator) of above - described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above - described well as filled that the same are true and correct, so help me God.


(Signature) Randy Newberry

(Address) PO Box 195, Attica, KS 67009

SUBSCRIBED AND SWORN TO before me 17th day of March, 2004

Jane Swingle
Notary Public

My commission Expires: 1-6-2007



Form CP-4
Revised 05-88

ALLIED CEMENTING CO., INC. 15076

Federal Tax I.D. # ~~33-0000000~~

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Medicine Lodge

DATE <i>2-9-04</i>	SEC. <i>15</i>	TWP. <i>26S</i>	RANGE <i>9W</i>	CALLED OUT <i>7:30 Am</i>	ON LOCATION <i>8:30 Am</i>	JOB START <i>9:15 Am</i>	JOB FINISH <i>12:30 pm</i>
LEASE <i>Adkins</i> WELL# <i>1</i>			LOCATION <i>Penalosa, Ks, North to</i>		COUNTY <i>Kingman</i>	STATE <i>KS</i>	
OLD OR NEW (Circle one)			<i>Pretty Prairie Rd 1 1/2 E, N/S</i>				

RECEIVED
MAR 18 2004
KCC WICHITA

CONTRACTOR *Quality Well Service* OWNER *R+B Oil + Gas*

TYPE OF JOB *OH P*

HOLE SIZE _____ T.D. _____ CEMENT _____

CASING SIZE *5 1/2* DEPTH *1300'* AMOUNT ORDERED _____

TUBING SIZE *8 7/8 casing* DEPTH *2351* *230 sx 60:40:4 2/3 cc*

DRILL PIPE _____ DEPTH _____ *3 sx cc*

TOOL _____ DEPTH _____

PRES. MAX *450'* MINIMUM _____ COMMON *1.38 @ 7.15 986.70*

MEAS. LINE _____ SHOE JOINT _____ POZMIX *92 @ 3.80 349.60*

CEMENT LEFT IN CSG. _____ GEL *8 @ 10.00 80.00*

PERFS. _____ CHLORIDE *3 @ 30.00 90.00*

DISPLACEMENT _____ @ _____

EQUIPMENT

PUMP TRUCK CEMENTER *Carl Selding* HANDLING *241 @ 1.15 277.15*

#*343* HELPER *Dave Felio* MILEAGE *35 x 241 x .05 421.75*

BULK TRUCK #*364* DRIVER *Travy Cushmanberry*

BULK TRUCK # _____ DRIVER _____ TOTAL *2205.20*

REMARKS:

SERVICE

Pump 35 sx 60:40:2+3/4 cc - 1300' DEPTH OF JOB *1300'*

35 sx 60:40:4+3/4 cc - 800' PUMP TRUCK CHARGE *475.00*

Circulate cement to surface EXTRA FOOTAGE _____ @ _____

from 280' with 160 sx 60:40:4 MILEAGE *35 @ 3.50 122.50*

PLUG _____ @ _____

_____ @ _____

_____ @ _____ TOTAL *597.50*

CHARGE TO: *R+B Oil + Gas*

STREET _____

FLOAT EQUIPMENT

CITY _____ STATE _____ ZIP _____

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____ TOTAL _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____
TOTAL CHARGE *[Signature]*
DISCOUNT *[Signature]* IF PAID IN 30 DAYS

SIGNATURE *David Brady*

ANY APPLICABLE TAX WILL BE CHARGED UPON INVOICING. PRINTED NAME _____