

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas. 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

00751
 15-147-~~00752~~-00-00

API NUMBER N/A

LEASE NAME Davis

WELL NUMBER 5

3630 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 32 TWP. 1 RGE. 18 ~~(E) (W)~~

COUNTY Phillips

Date Well Completed Dec. 1950

Plugging Commenced 8/7/85

Plugging Completed 8/7/85

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Petroleum Management, Inc.

ADDRESS 400 N. Woodlawn, Suite 201, Wichita, KS 67208

PHONE#(316) 686-7287 OPERATORS LICENSE NO. 5242

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? N/A If not, is well log attached? N/A

Producing Formation Lansing-K.C. Depth to Top 3407' Bottom 3527' T.D. 3527'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing-K.C.	Oil	3430	34			
		3465	68	8 5/8	240	None
		3482	85			
		3505	08	5 1/2	3527	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped down 8 5/8 w/75 sx cement w/2 sx hulls (27 Bbl) - 12 sx gel (24 Bbl) - 75 sx cement (27 Bbl). Hook to 5 1/2". Pump 150 sx cement w/2 sx hulls (53 Bbl) - wiper plug - 50 sx cement (18 Bbl). Cement 60-40 Pozmix, 10% gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Petroleum Management, Inc. License No. 731

Address Box H, Plainville, Ks. 67663

STATE OF Kansas COUNTY OF Sedgwick, ss.


R. D. Reber (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. D. Reber Jr.

(Address) 400 N. Woodlawn, Wichita, Ks 67208

STATE CORPORATION COMMISSION
 RECEIVED
 9-6-85
 SEP 6 1985
 SUBSCRIBED AND SWORN TO before me this 30th day of August, 19 85

My Commission Expires:
 CONSERVATION DIVISION
 Wichita, Kansas



Bonnie Brown
 Notary Public