


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Decatur County, Sec. 2 Twp. 1S Rge. 29W ~~X0EY~~ (W)
Location as "NE/CNW/SW" or footage from lines SE SE SE
Lease Owner Okmar Oil Co.
Lease Name ~~XXXXXXXXXXXXXXXXXXXX~~ Moore Well No. A-#1
Office Address 1130 Wichita Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-28-67 19
Application for plugging filed 10-28-67 19
Application for plugging approved 10-28-67 19
Plugging commenced 10-28-67 19
Plugging completed 10-28-67 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 2396 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	251'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bridged hole @ 1600' cemented with 100 sks. cement through drill pipe
Set Plug @ 260' with 20 sks. cement; bridged w/ 1/2 sk. hulls, plug @
40' w/10 sks. cement
2 sks. cement in rathole

RECEIVED
CONSERVATION DIVISION

NOV 6 1967

11-6-1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

Box 486, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of October, 1967

Mlanda Nichols
Notary Public.

My commission expires April 1, 1971

DRILLER'S LOG

COMPANY : Okmar Oil Company
 CONTRACTOR : LEBEN DRILLING, INC.
 FARM: MOORE A-#1
 LOCATION: SE SE SE SECTION 2-1S-29W
 DECATUR COUNTY, KANSAS
 COMMENCED: 10-24-67
 COMPLETED: 10-28-67

0	50	Surface Clay
50	251	Sand, Shale
251	1237	Shale
1237	1790	Sand, Shale
1790	2020	Shale, Lime
2020	2358	Shale
2358	2386	Anhydrite
2386	2396	Shale
	<u>2396</u>	<u>RTD - D. & A.</u>

RECEIVED
 NOV 6 1967
 11-6-1967
 DIVISION
 KANSAS

8 5/8" 8 rd. 24# used surface casing set @ 251' cemented with 200 sacks Common, 2% cc

I, Leslie Kite, do hereby certify that the foregoing is a true and correct copy of the log of the Moore A-#1 Well, located SE SE SE of Section 2, 1 South Township, and Range 29 West, Decatur County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 31st day of October, 1967.

Ulanda Nichols
 Ulanda Nichols

My Commission Expires:
 April 1, 1971